

All pavement construction shall be in conformance with the typical cross section shown on the plans and in conformance with the State of Wisconsin Department of Transportation "Standard Specifications for Road and Bridge Construction", All work shall be in accordance with City of Milton Standards.

The contractor shall clear, grub, and dispose of all brush, stumps, trees, etc., within the construction limits of the subject property and within the construction limits of all sewer and water main construction. Contractor shall remove those materials from the work site and dispose of them at the contractor's option and in conformance with State and local regulations.

Contractor shall verify location of any existing utilities prior to excavation. Call Digger's Hotline before digging (1 800 242-8511). Contractor shall backfill any utilities in structural areas using appropriate granular backfill.

Permits shall be obtained for any street openings.

All work shall be in accordance with "Wisconsin Construction Site Best Management Practices Handbook", latest edition.

Contractor shall notify the City of Milton 48 hours prior to start of construction.

Contractor shall ensure drive approaches shall be in accordance with City of Milton specifications (unless changes are approved by the City).

STANDARD INSTALLATION

SIDE PROTECTION INSTALLATION

THE SIDE PROTECTION INSTALLATION SHALL BE USED WHERE FROST WILL PENETRATE BELOW THE PIPE INVERT.

ALL PIPING: CAST IRON OR PVC 4" DIA.

NEENAH #R-6462-GH (P6462-220) LETTER

#4 REBAR 6" O.C.

TOP UNCAPPED (TYP.)

LIQUID LEVEL (LL) -

PLUMBING CONTRACTOR TO VERIFY ALL DIMENSIONS WITH JOB SITE INVERT ELEVATIONS. BEFORE ORDERING GREASE BASIN.

1,500 GALLON GREASE BASIN DETAIL

1/3 LL

E/W AS SHOWN -

N 4" SANITARY TEE

2" MIN

INLET INVERT INLET | TO

TO STATE "GREASE INTERCEPTOR"

# SITE SPECIFIC NOTES

All construction debris must be removed from site. In no instance shall debris be buried on-site.

Contractor shall verify all public & private utilities are installed prior to laying gravel.

Contractor shall provide unit prices to owner at time of bid for removal and replacement of unsuitable material under structures and traffic areas as approved by owner.


# GREASE INTERCEPTOR CALC. $C = S \times H \times A \text{ WHERE}$ S = NUMBER OF SEATS, WITH EACH DRIVE-IN CAR SERVICE SPACE COUNTING AS 3 SEATS AND EACH DRIVE-UP SERVICE WINDOW COUNTING AS 60 SEATS. H = HOURS PER DAY THAT MEALS ARE SERVED, AT LEAST 6 HOURS BUT NOT MORE THAN 12 HOURS. A = APPLIANCE FACTOR: 0.75 FOR A KITCHEN WITH NO DISHWASHING MACHINE AND NO FOOD WASTE GRINDER. 1.0 FOR A KITCHEN WITH EITHER A DISHWASHING MACHINE OR A FOOD WASTE GRINDER. 1.25 FOR A KITCHEN WITH BOTH A DISHWASHING MACHINE AND A FOOD WASTE GRINDER THIS PROJECT: S = 156 (96 SEATS, 60 SEATS DRIVE-THRU) H = 12 HOURS A = 0.75C = 1,404


ALL PAPER SERVICE (SIZE MAY BE HALVED) 1.404/2 = 702

MINIMUM 750 GALLON REQUIRED (DISCH. TO MUNICIPAL SEWER)


# EXTERIOR GREASE INTERCEPTOR NOTES:


- THE TANK MUST COMPLY WITH PARTS 5 & 6 OF ASTM STANDARD c1613. THE NAME OF THE TANK MANUFACTURER, THE LIQUID HOLDING CAPACITY, AND COMPLIANCE WITH ASTM c1613 FOR TANK CONSTRUCTION MUST BE PERMANENTLY AFFIXED TO THE TANK.
- THE INTERCEPTOR MUST BE PROTECTED FROM FREEZING BASED ON INSTALLATION DEPTH AND SOIL TYPE PER WISCONSIN ADMINISTRATIVE CODE SPS 382.30(11)(c). THE LANDSCAPE MUST BE BERMED TO DIVERT RUN-OFF. THE TANK MUST BE PROTECTED TO PREVENT LOADING THAT MAY LEAD TO STRUCTURAL COLLAPSE.
- THE TANK MUST BE READILY ACCESSIBLE FOR INSPECTION AND MAINTENANCE.
- THE MATERIAL USED IN PIPING TO THE INLET OF THE TANK MUST COMPLY WITH BUILDING DRAIN REQUIREMENTS. THE TANK OUTLET PIPING MAY COMPLY WITH BUILDING SEWER MATERIALS, UNLESS THE OUTLET PIPING REENTERS THE BUILDING. IN SUCH CASES, MATERIALS SHALL BE APPROVED FOR BUILDING DRAIN. THE INLET AND OUTLET PIPES MUST BE CONNECTED TO THE TANK WITH A SEALED FLEXIBLE JOINT TO ACCOMMODATE PIPE MOVEMENT. A CLEANOUT MUST PROVIDED ON THE DISCHARGE LINE FROM THE INTERCEPTOR
- THE TANK AND BAFFLE DESIGN MUST ALLOW FOR CONTINUOUS CIRCULATION OF AIR THROUGHOUT THE TANK. PROVIDE 2"Ø VENT INTO BUILDING - SEE PLUMBING PLANS.
- INSPECTION PIPES LOCATED ABOVE THE BAFFLES/TEES AND A MANHOLE MUST BE PROVIDED. THE MANHOLE COVER MUST BE LOCKED IN PLACE; MARKED WITH WARNING TO NOT ENTER WITHOUT PROPER EQUIPMENT; AND TO BE PROVIDED WITH A LABEL IDENTIFYING THE VESSEL AS THE EXTERIOR GREASE INTERCEPTOR.
- AFTER INSTALLATION, THE TANK MUST PASS A MANOMETER TEST WITH 1 INCH OF WATER COLUMN FOR 5 MINUTES, OR A VACUUM TEST WITH 2 INCHES OF MERCURY FOR 60 MINUTES. THE GREASE INTERCEPTOR MUST BE INSPECTED AT LEAST ONCE EVERY 3 MONTHS, AND MUST BE PUMPED AND CLEANED REGULARLY. THE RECORDS OF THE INSPECTION MUST BE KEPT FOR AT LEAST 3 YEARS.
- INTERCEPTORS LOCATED IN TRAFFIC AREAS SHALL BE DESIGNED TO WITHSTAND AN AASHTO-H20-44 WHEEL LOAD.






# WATER SERVICE DETAIL







DIRECTION OF FLOW

PLUG WYE IF SERVICE LATERAL

SEE PLAN FOR PIPE SIZE, TYPE, AND ELEVATION




COMPACTED TRENCH


IN GRASS AREAS

EXISTING & PROPOSED


BACKFILL UNDER AND WITHIN 2 FEET OF ANY PAVEMENTS

-COMPACTED NATURAL EARTH







DOWNSPOUT CONNECTION TO COLLECTOR PIPE DETAIL




TYPICAL RAISED SIDEWALK





# CONCRETE WALK DETAIL (THROUGH DRIVEWAYS)

INSTALL 3/4" EXPANSION JOINTS WHERE WALK ABUTS CURB, BUILDING OR WALL. INSTALL CONTROL JOINTS AT 5' INTERVALS



# STANDARD ACCESSIBLE DIMENSIONING

A U.S. DEPARTMENT OF TRANSPORTATION R7-8 (RESERVED PARKING) AND SUPPLEMENTAL SIGNS AS NOTED ABOVE MUST BE MOUNTED ON A PERMANENT POST NO LOWER THAN FROM THE PAVEMENT. THE POST MUST BE MOUNTED IN THE CENTER OF THE 8 FOOT WIDE ACCESSIBLE PARKING SPACE, NO MORE THAN 5 FEET FROM THE FRONT OF THE PARKING SPACE, SEE ILLUSTRATION ABOVE.


EACH ACCESSIBLE PARKING SPACE IS TO BE A MINIMUM OF 8 FEET WIDE AND HAVE A 96" MINIMUM ACCESS AISLE FOR VANS OR 60" ACCESS AISLE FOR CARS ADJACENT TO THE SPACE. THE ACCESS AISLE MAY BE ON EITHER THE DRIVER'S SIDE OR THE PASSENGER'S SIDE OF THE ACCESSIBLE SPACE. THIS APPLIES TO 45, 60, AND 90 PARKING.

ACCESSIBLE PARKING SPACES ARE TO BE LOCATED AS CLOSE TO THE STORE ENTRANCE AS POSSIBLE AND SHALL BE IDENTIFIED WITH A SIGN.

ACCESSIBLE PARKING SPACES AND ACCESS AISLES SHALL BE LEVEL WITH A SLOPE OF 1 1/2% (2% MAXIMUM)(EXAMPLE: 1.92 INCHES MAX. VERTICAL IN & FEET HORIZONTAL) OR 1:50 IN ALL DIRECTIONS. THIS INCLUDES BOTH "RUNNING SLOPES" AND "CROSS SLOPES."


THE ACCESS AISLE SHALL BE DESIGNATED WITH HIGH QUALITY YELLOW DIAGONAL SURFACE PAINT STRIPING.

ADA ALLOWS TWO PARKING SPACES TO SHARE AN ACCESS




(OR APPROVED EQUAL)


(OR APPROVED EQUAL)




-ADJACENT PAVEMENT 6" CONCRETE CURB SAW 1/8" WIDE X 2" WIDE DEEP & FILL OR VINYL STRIP FOR CONTRACTION JOINT AT 25' INTERVALS THRU CURB. 3/4" PREMOLDED EXPANSION JOINT AT RADIUS RETURNS, STRUCTURES & 100' MAXIMUM SPACING. • LAND SURVEYING 08/10/20 08/18/20 Storm,Pvmt Det. AF LAND PLANNING CIVIL ENGINEERING APPROVED

& ASSOCIATES 109 W. Milwaukee St tel: 608 752-0575 PROJECT NO. Janesville, WI 53548 fax: 608 752-0534 120-295 www.combssurvey.com







#### GENERAL EROSION NOTES

- . THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS COMPRISED OF THIS DRAWING, THE EROSION CONTROL DETAILS, THE NOI PERMIT, SUBSEQUENT REPORTS AND RELATED DOCUMENTS.
- B. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THE SWPPP AND THE STATE OF WISCONSIN NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM GENERAL PERMIT (NPDES PERMIT) AND BECOME FAMILIAR WITH THEIR CONTENTS.
- CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES (BMP's) AS REQUIRED BY THE SWPPP. ADDITIONAL BMP'S SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AT NO ADDITIONAL COST OF THE OWNER THROUGHOUT ALL PHASES OF CONSTRUCTION.
- BEST MANAGEMENT PRACTICES AND CONTROLS SHALL CONFORM TO FEDERAL, STATE, OR LOCAL REQUIREMENTS, OR MANUAL OF PRACTICE, AS APPLICABLE. CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS DIRECTED BY PERMITTING AGENCY OR OWNER.
- THE SITE MAP MUST CLEARLY DELINEATE ALL STATE WATERS AND PERMITS FOR ANY CONSTRUCTION ACTIVITY IMPACTING STATE WATERS OR REGULATED WETLANDS, AND MUST BE MAINTAINED ON-SITE
- CONTRACTOR SHALL MINIMIZE CLEARING TO THE MAXIMUM EXTENT PRACTICABLE OR AS REQUIRED BY THE GENERAL PERMIT
- GENERAL CONTRACTOR SHALL DENOTE ON PLAN THE TEMPORARY PARKING AND STORAGE AREA WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREA, EMPLOYEE PARKING
- AREA, AND AREA FOR LOCATING PORTABLE FACILITIES, OFFICE TRAILERS, AND TOILET FACILITIES. H. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND PROPERLY TREATED OR DISPOSED
- SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOATATION BOOMS SHALL BE MAINTAINED ON-SITE OR READILY AVAILABLE TO CONTAIN AND CLEAN UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- . DUST ON THE SITE SHALL BE CONTROLLED. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.
- RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORM WATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE.
- ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THIS PLAN, AND IN THE SWPPP SHALL BE INITIATED AS SOON AS PRACTICABLE.
- M. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS STOPPED FOR AT LEAST 14 DAYS SHALL BE TEMPORARILY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS.
- . DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE PERMANENTLY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 14 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS. REFER TO THE GRADING PLAN AND/ OR LANDSCAPING PLAN.
- IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION ENTRANCES IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF THE SITE.
- ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.
- . CONTRACTORS OR SUBCONTRACTORS SHALL BE RESPONSIBLE FOR REMOVING SEDIMENT IN THE DETENTION PONDS AND ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM SEWER DRAINAGE SYSTEMS IN CONJUNCTION WITH THE STABILIZATION OF THE SITE.
- ON-SITE & OFF-SITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BEST MANAGEMENT PRACTICES. STOCKPILE AND BORROW AREA LOCATIONS SHALL BE NOTED ON THE SITE MAP AND PERMITTED IN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS.
- 5. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION
- DUE TO THE GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION CONTROL MEASURES (SILT FENCES, STRAW BALES, ETC.) TO PREVENT EROSION.
- . ALL CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY. THIS INCLUDES BACKFILLING OF TRENCHES FOR UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD CONSTRUCTION

## **EROSION CONTROL PLAN NOTES:**

1. PHASED CONSTRUCTION / STABILIZATION

TO ENSURE THAT DISTURBED AREAS ARE NOT VULNERABLE TO EROSION FOR EXTENDED PERIODS, THE SITE NEEDS TO BE BROKEN INTO ZONES OF LAND DISTURBANCE.

WITHIN EACH ZONE, STABILIZE (E.G., SEED & MULCH, COMPOST, EROSION MAT, POLYMER) ALL DISTURBED AREAS OUTSIDE OF STREET RIGHT-OF-WAY BEFORE BREAKING GROUND IN THE NEXT ZONE. STABILIZATION SHALL OCCUR WITHIN 30 DAYS OF INITIAL GROUNDBREAKING OR WITHIN 7 DAYS OF ACHIEVING FINAL GRADE, WHICH EVER OCCURS FIRST

MULCH AS PART OF A STABILIZATION MEASURE SHALL BE APPLIED TO PRODUCE A CONTINUOUS COVER OF MULCH AND SHALL BE ANCHORED AT A RATE OF 2 TONS PER ACRE. IN ALL CASES, THE MULCH MUST BE ANCHORED INTO THE SOIL BY DISCING.

2. CONSTRUCTION ENTRANCES/EXITS

CONTRACTOR SHALL PROVIDE A STONE TRACKING PAD AT THE POINT(S) OF ACCESS AS SHOWN ON THE PLANS. INSTALL ACCORDING TO WDNR STANDARD 1057. REFER TO WDNR'S WEB PAGE OF TECHNICAL STANDARDS AT: http://dnr.wi.gov/org/water/wm/nps/stormwater/techstds.htm#Construction

3. WATER PROVISION

FOR THE FIRST SIX WEEKS AFTER INITIAL STABILIZATION (E.G., SEED & MULCH, EROSION MAT, SOD) OF A DISTURBED AREA, PROVISION SHALL BE MADE FOR WATERING WHENEVER MORE THAN 7 DAYS OF DRY WEATHER ELAPSE.

4. TEMPORARY STABILIZATION USING ANIONIC POLYMER

ANIONIC POLYACRYLAMIDE WILL BE APPLIED TO ALL DISTURBED AREAS WHERE THE VILLAGE ENGINEER OR WDNR REPRESENTATIVES DEEM STABILIZATION AND/OR EROSION TO BE PROBLEMATIC. APPLICATION OF POLYACRYLAMIDE WILL BE ACCORDING TO WDNR CONSERVATION PRACTICE STANDARD 1050, EROSION CONTROL LAND APPLICATION OF ANIONIC POLYACRYLAMIDE. REFER TO WDNR'S STORMWATER

WEB PAGE OF TECHICAL STANDARDS AT: http://dnr.wi.gov/org/water/wm/nps/stormwater/techstds.htm 5. DEEP TILLING

FOLLOWING ROUGH GRADING, DEEP TILLING (A.K.A. SUBSOILING) WILL BE PERFORMED ON ALL GRADED AREAS OUTSIDE THE FOOTPRINT OF STREET FOOTPBINTS. THE OPERATION ALL GHADED AREAS OUTSIDE HEE FOOTPHINT OF STREET FOOTPHINS. THE OPERATION SHALL BE ACCOMPLISHED USING TWIN STRAIGHT STEEL SHANKS DRAWN BY TRACKED MACHINERY. EACH SHANK SHALL BE 24 TO 35 HICHES LONG, POSITIONED OVER THE TRACTOR TRACKS, AND SPACED 4 TO 5 FEET APART. DEEP TILLING SHALL BE DONE ON DRY SOIL AND ACROSS THE SLOPE. REFER TO THE DANE COUNTY EROSION CONTROL AND STORMWATER MANAGEMENT MANUAL APPENDIX I.D. 1, WHICH IS ACCESSIBLE FROM THE DANE COUNTY LAKES AND WATERSHED COMMISSION WEB SITE AT:

http://www.countyofdane.com/lwrd/lakes/stormwatermanual.shtml

6. SOIL STOCKPILES

A ROW OF SILT FENCE PLACED DOWNSLOPE AND AT LEAST 10 FEET AWAY FROM SOIL STOCKPILES SHALL PROTECT ALL STOCKPILES. SOIL STOCKPILES THAT ARE INACTIVE FOR MORE THAN 14 CONSECUTIVE DAYS SHALL BE STABILIZED WITH SEED & MULCH, EROSION MAT. POLYMER, OR COVERED WITH TARPS OR SIMILAR MATERIAL

WATER PUMPED FRO SITE SHALL BE TREATED BY USING A TEMPORAR BASIN, PORTABLE DEWATERING BASIN OR AN EQUIVALENT DEVIC

WE A DEPTH OF AT LEAST 3 FEET AND ANY INDIVIDUAL SEDIMENTATION BASIN\_S PROVIDE A MAXIMUM SURFACE SETTLING RATE OF GALLONS PER SQUARE FOOT PER DAY. THIS WATER\_SHALL BE DISCHARGED IN A MANNER THAT DOES NOT INDUCE EROSION OF

THE SITE OR ADJACENT PROPERTY 8. STORM SEWER INLETS

PROVIDE WDOT TYPE D "CATCHALL" INLET PROTECTION OR EQUIVALENT. REFER TO WDOT PRODUCT ACCEPTABILITY LIST AT: http://www.dot.wisconsin.gov/business/engrserv/pal.htm. INLET PROTECTION SHALL BE INSTALLED PRIOR TO THE STORM SEWER SYSTEM RECEIVING SITE RUNOFF. OTHER THAN FOR PERFORMING MAINTENANCE, THESE DEVICES SHALL NOT BE REMOVED UNTIL FLAT-LEVEL STABILIZATION IS COMPLETE.

9. INSPECTIONS

ALL EROSION CONTROL MEASURES AND STRUCTURES SERVING THE SITE MUST BE INSPECTED AT LEAST WEEKLY AND WHENEVER 0.5 INCHES OF RAIN OR MORE IS PRODUCED WITHIN 24 HOURS. ALL NECESSARY MAINTENANCE SHOULD FOLLOW THE INSPECTIONS WITHIN 24 HOURS.

THE STORM WATER PONDS SHALL BE CONSTRUCTED TO ALLOW SEDIMENTATION WITHIN THE POND DURING CONSTRUCTION (EXCLUDING BIO-FILTERS), AND THE CLEANING OF THE POND FROM ACCUMULATED SEDIMENT AT THE COMPLETION OF CONSTRUCTION

#### **MAINTENANCE**

ALL MEASURES STATED ON THIS EROSION AND SEDIMENT CONTROL PLAN, AND IN SWPPP SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON IN ACCORDANCE WITH THE CONTRACT DOCUMENTS OR THE APPLICABLE PERMIT, WHICHEVER IS MORE STRINGENT, AND REPAIRED IN ACCORDANCE WITH THE FOLLOWING:

- 1. INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED OR REPLACED IF THEY SHOW SIGNS OF UNDERMINING. OR DETERIORATION.
- 2. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED. WATERED. AND RESEEDED AS NEEDED.
- 3. SILT FENCES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES WHEN IT REACHES ONE-HALF THE HEIGHT OF THE SILT FENCE.
- 4. THE CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH SHALL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION ENTRANCE AS CONDITIONS DEMAND.
- 5. THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING
- 6. OUTLET STRUCTURES IN THE SEDIMENTATION BASINS SHALL BE MAINTAINED IN OPERATIONAL CONDITIONS AT ALL TIMES. SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS OR TRAPS WHEN THE DESIGN CAPACITY HAS BEEN REDUCED.

## CONSTRUCTION SEQUENCE:

#### PHASE 1


- 1. Install construction entrance/exit(s).
- 2. Prepare temporary parking and equipment storage area.
- . Install silt fencing where indicated. Construct the vegetated infiltration swales & corresponding silt fencing.

HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEERING CONSULTANT TO PERFORM AN INSPECTION OF BEST MANAGEMENT PRACTICES (BMP's). GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT A STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION.


5. Clear and grub the site. 6. Begin grading the site

- 1. Temporarily seed denuded areas.
- . Install utilities, underdrains, storm sewers. . Install matting/rip-rap around outlet structures per detail.
- . Install inlet protection around indicated storm sewer inlets. 5. Stabilize all areas that are to be seeded and able to be brought
- to finished grade with seeding/mulch, sod, or approved equal.
- 6. Stabilize all areas that are to be paved and that are able to be prought to supgrade elevation with compacted pase material.
- 7. Grade all possible areas while maintaining diversions and basins.
- 8. Stabilize all areas that are to be seeded and able to be brought to finished grade with seeding/mulch. sod. or approved equal.
- 9. Stabilize all areas that are to be paved and that are able to be brought to subgrade elevation with compacted base material.
- 10. Maintain 70% stabilization within disturbed areas.


- . Backfill and stabilize diversions and swales.
- 2. Pave site.
- 4. Remove all temporary erosion and sediment control devices (only if site is stablized)



# STONE TRACKING PAD FOR MORE INFORMATION, SEE DNR BMP TECH STANDARD 1057



# SILT FENCE



TIEBACK BETWEEN FENCE POST AND ANCHOR — SILT FENCE

TRENCH DETAIL

SILT FENCE TIE BACK WHEN REQUIRED BY ENGINEER

